



PUBLIC MAINTENANCE PIPE SCHEDULE - TO BE MAINTAINED BY THE CITY		
SIZE	TYPE	LENGTH (ft)
15"	RCP Class IV	13

PUBLIC STRUCTURE SCHEDULE - TO BE MAINTAINED BY THE CITY					
No.	Type & Standard	Inside Dimensions or Diameter	Elev.	Notes	
12	Precast "A10" Curb Inlet per MC-501.01	Open Box 2.5x1'0"	LT TC = 463.72 RT TC = 463.26	Prior to Ordering Structure - Confirm Adequate Clearance Between Location & Ex. Power Conduit	
10	Precast 48" Dia. Manhole per MC-510.01	48"	Top of MH = 462.75	*****	

Precast and Contractor must refer to the Approved Soil Erosion, Sediment Control and SWM Plans for any Temporary EESC Pipes and/or SWM Pipes and structures.

MANHOLE COVER: Note All manhole covers for all inlets and manholes are to be per Montgomery County Standards per MC-501.01 and MC-510.01

Before beginning any work, any non-standard precast cast-in-place concrete structural drawings for this construction must be reviewed and approved by the City of Galveston and the Engineer prior to any fabrication and/or construction.

